

PROJECT #6427782

Project consists of isolated shell and core improvements to the downtown Macy's building.

PROPOSED SCOPE OF WORK SUMMARY

INTERIOR ELEMENTS

ITEM 1. REMOVE INTERIOR STAIRS 8 & 10. REMOVE AND STORE HANDRAILS & BALUSTRADE.

ITEM 2. REMOVE PORTION OF LEVEL 1 CEILING TO CREATE A NEW VERTICAL TRANSPORTATION CONNECTION TO OFFICE LOBBY AT LEVEL 2.

EXTERIOR ELEMENTS

ITEM 3. INSTALLATION OF (PSE) AMR ANTENNA FOR RETAIL TENANT.
ITEM 4. SECURITY ENHANCEMENTS. INSTALLATION OF NEW 360-DEGREE CAMERAS.


ITEM 5. REPAIR OF MARQUEE (CANOPY).
ITEM 6. RESTORE DISPLAY WINDOW.

SUMMARY OF LANDMARK CONTROLLED ITEMS PER LANDMARKS ORDINANCE 114772:

(See copy of the original ordinance at the end of this document)


- Exterior of the building including roof and marquee
- Decorative ornament of first floor ceiling and columns
- Elevator wall surrounds
- 2 Sets of stair railings located on the first floor





3rd & Pine Redevelopment Project 24 AUGUST 2020

1/32"=1'-0"



1/32"=1'-0"



INTERIOR

ITEM 1. EXISTING STAIRS #8 & #10 TO BE REMOVED.

SCOPE OF WORK

- -REMOVE INTERIOR STAIRCASES #8 & #10.
- -REMOVE & STORE CHEVRON, GEOMETRIC METAL BALUSTRADE & HANDRAILS.
- -INFILL FLOOR OPENINGS.


300 Pine




EXISTING STAIR #10; REMOVE EXISTING STAIR #10. NEW FLOOR SLAB TO INFILLED BETWEEN LEVEL 1 AND BASEMENT LEVEL 1. REMOVE AND STORE HANDRAILS & BALUSTRADE.

Seattle, WA

3rd & Pine Redevelopment Project 24 AUGUST 2020



EXISTING STAIR #8. REMOVE EXISTING STAIR #8. NEW FLOOR SLAB TO INFILLED BETWEEN LEVEL 1 AND MEZZANINE LEVEL (3RD AVENUE STREET LEVEL). REMOVE AND STORE HANDRAIL & BALUSTRADE



KEY PLAN



INTERIOR

ITEM 2. LEVELS 1 & 2 NEW TWO STORY VERTICAL TRANSPORTATION.

SCOPE OF WORK

-REMOVE 2 BAYS OF LEVEL 2 FLOOR STRUCTURE FOR NEW STAIR AND ESCALATOR AND PORTION OF THIRD BAY FOR ELEVATOR HOISTWAY.

-REMOVE SECTIONS OF EXISTING "DECORATIVE TRIM" FALSE BEAM WORK TO ALLOW FOR STRUCTURAL DEMOLITION ABOVE.

-INSTALL EXACT REPLICAS "DECORATIVE TRIM" FALSE BEAM WORK AS INDICATED.





NOTE

*HISTORIC DECORATIVE PLASTER: HEMP FIBER BINDER & PLASTER.

NEW DECORATIVE PLASTER
WORK TO BE FORMED FROM
MOLDS MADE FROM THE
EXISTING HISTORIC TRIM AND
CAPITAL, COMPOSED OF THE
SAME MATERIALS & FINISHED TO
MATCH EXISTING HISTORICAL
ELEMENTS.






DECORATIVE PLASTER TRIM AT FALSE BEAMS*.
SEE NOTE ABOVE.


EXISTING HISTORIC DECORATIVE PLASTER COLUMN CAPITAL*. SEE NOTE ABOVE.

EXISTING COLUMN SHAFT.

DIRECT APPLIED PLASTER
TO CONCRETE COLUMN.


CALLISONRTKL






GRID


GRID






SEE SCOPE OF WORK NOTES ON THE NEXT SHEET.









VIEW


















24 AUGUST 2020















3rd & Pine Redevelopment Project

24 AUGUST 2020




ENLARGED DETAIL 11 | SECTION AT LEVEL 1 CEILING

1" = 1'-0"

300 Pine









EXTERIOR

ITEM 3. INSTALLATION OF NEW REMOTE READ AMR ANTENNA (AS REQUIRED BY PUGET SOUND ENERGY) & NEW NEMA 3 ENCLOSURE.

ITEM 4. INSTALLATION OF SECURITY ENHANCEMENTS. SCOPE OF WORK.


-INSTALLATION NEW 360 DEGREE CAMERA SYSTEM


ITEM 5. REPAIR OF DAMAGED MARQUEE. SCOPE OF WORK.

- -REPAIR OF DAMAGED MARQUEE SECTIONS.
- -REPLACE SECTIONS THAT ARE BEYOND REPAIR WITH THE SAME MATERIAL, FINISH AND ORNAMENT FOR A SEAMLESS REPAIR.



300 Pine







AMR ANTENNA EXTENDING 8" OUT THE TOP OF BOX BELOW.



ITEM 4. ANETNNA & MOUNTING BOX



ITEM 4.1 NEW SECURITY CAMERA





ITEM 4.1
EXISTING SECURITY CAMERA

CALLISONTKL




TYPICAL NEW SECURITY CAMERA LOCATION (UNLESS NOTED OTHERWISE).









SURFACE MOUNT

avigiLon ******

Order one of:

Camera module

H4AMH-AD-DOME1

H4AMH-DO-COVR1 or H4AMH-DO-COVR1-SMOKE


ITEM 4. SECURITY CAMERA CUT SHEETS




ITEM 5.1 REPAIR DAMAGE TO MARQUEE CANOPY FASCIA.
REPLACE WITH IN-KIND STAMPED COPPER PLATES - WEST ELEVATION



ITEM 5.1 REPAIR DAMAGE TO MARQUEE CANOPY SOFFIT.
REPLACE WITH IN-KIND FABRICATED COPPER SOFFIT - WEST ELEVATION






1/32"=1'-0"

EXISTING TO REMAIN (SHOWN GRAY SCALE)

PROPOSED WORK

300 Pine



Seattle, WA

3rd & Pine Redevelopment Project

24 AUGUST 2020

CALLISONTKL



EXISTING TO REMAIN (SHOWN GRAY SCALE)

PROPOSED WORK



EXTERIOR

ITEM 6. 4TH AVENUE & PINE STREET STOREFRONT RESTORATION.
SCOPE OF WORK

-REMOVE EXISTING ALL GLASS DOOR ASSEMBLY & RESTORE CORNER DISPLAY GLASS & FRAME TO MATCH HISTORIC CONFIGURATION & MATERIALS.

